

Cost Estimate Sheet

Date:

6-2-2026

Name:

Aurora

Location:

Trade:

Description:

6" T.W S&R

By:

UNIT PRICE

Quantity	Description	Material	Labor	Material	Labor
840'	6" Sch 10 304 S/S Roll Grooved				
60	6" S/S Roll Grooved Couplings				
2	6" S/S Lug Butterfly Valves w/GO and chain operators				
2	Sets of Bolts for 6" Lug Butterfly Valves S/S				
2	6" 150# S/S Gate Valves				
2	6" 150# Flange Bolt sets				
8	6" R/G Flange Adapters S/S				
2	6"x2" Concentric Reducers Sch 10 304 S/S				
4	6" Flange Washers				
8	6" Sch 10 304 S/S 90° Elbows				
84	6" S/S Clovis Hangers				
32	2" 3-piece Ball Valves w/ welded Tail pieces				
30	2" sock-o-lots 304 S/S				
420'	3/4" S/S All Thread				
168	3/4" S/S Nuts				
168	3/4" Locking Nuts				
336	3/4" Flat Washer S/S				
21'	2" Sch 40 304 S/S Pipe				
10 QTS	R/G Lub				

Alternate

Branch Lines

84'	2" Mega Press S/S Tube				
6	2" 90° Elbow S/S				
2	2" x 3/4" Fip S/S adapter				
2	2" 3-piece Ball Valves 304 S/S				
4	2" M/P S/S Mip Adapters				
1	2" S/S Y-Strainer				
2	2" M/P S/S Unions				
8	2" S/S Clovis Hangers				
80'	3/8" S/S All Thread				
32	3/8" S/S Nuts				
32	3/8" S/S Flat Washers				
		Mega Press		2 - 1/4" x 3" S/S Nipples sch 40	
				2 - 1/4" Ball Valves	
				2 - 1/4" x 3" S/S 1/2" Pressure gauges	
		Total:			